



GUIDELINE

ASHRAE Guideline 0-2019

(Supersedes ASHRAE Guideline 0-2013)

Includes ASHRAE addenda listed in Appendix Q

The Commissioning Process

See Informative Appendix Q for ASHRAE approval dates.

This Guideline is under continuous maintenance by a Standing Guideline Project Committee (SGPC) for which the Standards Committee has established a documented program for regular publication of addenda or revisions, including procedures for timely, documented, consensus action on requests for change to any part of the Guideline. Instructions for how to submit a change can be found on the ASHRAE® website (<https://www.ashrae.org/continuous-maintenance>).

The latest edition of an ASHRAE Guideline may be purchased from the ASHRAE website (www.ashrae.org) or from ASHRAE Customer Service, 1791 Tullie Circle, NE, Atlanta, GA 30329-2305. E-mail: orders@ashrae.org. Fax: 678-539-2129. Telephone: 404-636-8400 (worldwide), or toll free 1-800-527-4723 (for orders in US and Canada). For reprint permission, go to www.ashrae.org/permissions.

ASHRAE Standing Standard Project Committee 300

Cognizant TC: 7.9, Building Commissioning

SPLS Liaison: Susanna Hanson

ASHRAE Staff Liaison: Ryan Shanley

Harry J. Enck*, *Chair*
Walter T. Grondzik*†, *Vice-Chair*
Justin F. Garner*†, *Secretary*
Mina Agarabi†
Michael Amstadt*†, *Gdl. 0 Subcomm. Chair*
Curtis L. Anthony*
Allan Bilka
Alonzo B. Blalock*
Dean S. Borges
Barry B. Bridges†
Kristopher S. Brockles
Bradley A. Brooks
David L. Cantrill
Thomas E. Cappellin*†
Ryan Colker
Wade H. Conlan*
Timothy F. Corbett*†

David L. Edenburn
Steven C. Funk
David B. Green
Eric V. Hebel
Walter D. Horn†
Andrew A. Howard†
Gary E. Johnson
Gerald J. Kettler*†
Roger W. Lautz
James I. Magee*†
Sarah E. Maston
David C. Meyers
Ross D. Montgomery*
Ian C. Nelson
Lawrence D. Ollice
Jean-Francois Pelletier*
Bruce A. Pitts*†

Rod Rabold*
Lee Riback†
Terry L. Rodgers
Larry S. Ross†
Reinhard G. Seidl*
Andres J. Sepulveda
Justin T. Setert†
Mark E. Siira
Ole Teisen*
Terry E. Townsend
James K. Vallort
David Wall†
Tracey A. Whaley
Stephen R. Wiggins*
Jacqueline Wilmot

* Denotes members of voting status on SSPC 300 when the document was approved for publication

† Denotes members of Guideline 0 Subcommittee

ASHRAE STANDARDS COMMITTEE 2018–2019

Donald M. Brundage, *Chair*
Wayne H. Stoppelmoor, Jr., *Vice-Chair*
Els Baert
Charles S. Barnaby
Niels Bidstrup
Robert B. Burkhead
Michael D. Corbat
Drury B. Crawley
Julie M. Ferguson
Michael W. Gallagher

Walter T. Grondzik
Vinod P. Gupta
Susanna S. Hanson
Roger L. Hedrick
Rick M. Heiden
Jonathan Humble
Kwang Woo Kim
Larry Kouma
R. Lee Millies, Jr.
Karl L. Peterman

Erick A. Phelps
David Robin
Lawrence J. Schoen
Dennis A. Stanke
Richard T. Swierczyna
Rusty Tharp
Adrienne G. Thomle
Craig P. Wray
Lawrence C. Markel, *BOD ExO*
Michael CA Schwedler, *CO*

Steven C. Ferguson, *Senior Manager of Standards*

SPECIAL NOTE

This Guideline was developed under the auspices of ASHRAE. ASHRAE Guidelines are developed under a review process, identifying a Guideline for the design, testing, application, or evaluation of a specific product, concept, or practice. As a Guideline it is not definitive but encompasses areas where there may be a variety of approaches, none of which must be precisely correct. ASHRAE Guidelines are written to assist professionals in the area of concern and expertise of ASHRAE's Technical Committees and Task Groups.

ASHRAE Guidelines are prepared by Project Committees appointed specifically for the purpose of writing Guidelines. The Project Committee Chair and Vice-Chair must be members of ASHRAE; while other committee members may or may not be ASHRAE members, all must be technically qualified in the subject area of the Guideline.

Development of ASHRAE Guidelines follows procedures similar to those for ASHRAE Standards except that (a) committee balance is desired but not required, (b) an effort is made to achieve consensus but consensus is not required, (c) Guidelines are not appealable, and (d) Guidelines are not submitted to ANSI for approval.

The Senior Manager of Standards of ASHRAE should be contacted for

- interpretation of the contents of this Guideline,
- participation in the next review of the Guideline,
- offering constructive criticism for improving the Guideline, or
- permission to reprint portions of the Guideline.

DISCLAIMER

ASHRAE uses its best efforts to promulgate Standards and Guidelines for the benefit of the public in light of available information and accepted industry practices. However, ASHRAE does not guarantee, certify, or assure the safety or performance of any products, components, or systems tested, installed, or operated in accordance with ASHRAE's Standards or Guidelines or that any tests conducted under its Standards or Guidelines will be nonhazardous or free from risk.

ASHRAE INDUSTRIAL ADVERTISING POLICY ON STANDARDS

ASHRAE Standards and Guidelines are established to assist industry and the public by offering a uniform method of testing for rating purposes, by suggesting safe practices in designing and installing equipment, by providing proper definitions of this equipment, and by providing other information that may serve to guide the industry. The creation of ASHRAE Standards and Guidelines is determined by the need for them, and conformance to them is completely voluntary.

In referring to this Standard or Guideline and in marking of equipment and in advertising, no claim shall be made, either stated or implied, that the product has been approved by ASHRAE.

CONTENTS
ASHRAE Guideline 0-2019
The Commissioning Process

SECTION	PAGE
Foreword	2
1 Purpose	2
2 Scope	2
3 Utilization.....	2
4 Definitions	2
5 Predesign Phase.....	4
6 Design Phase.....	7
7 Construction Phase.....	11
8 Occupancy and Operations Phase	15
9 References.....	17
Normative Appendix A: Guide for Developing Supplementary Technical Guidelines for the Commissioning Process	18
Informative Appendix B: Commissioning Process Flowchart.....	21
Informative Appendix C: Cost and Benefits of the Commissioning Process	23
Informative Appendix D: Commissioning Process Documentation Matrix	24
Informative Appendix E: Commissioning Process Request for Qualifications	26
Informative Appendix F: Roles and Responsibilities	29
Informative Appendix G: Cx Plan	31
Informative Appendix H: Acceptance Plan	32
Informative Appendix I: Owner's Project Requirements Workshop Guidance	34
Informative Appendix J: Owner's Project Requirements	36
Informative Appendix K: Basis of Design	39
Informative Appendix L: Specifications	40
Informative Appendix M: Construction Checklists	46
Informative Appendix N: Quality-Based Sampling Examples.....	51
Informative Appendix O: Systems Manual	54
Informative Appendix P: Training Manual and Training Needs	56
Informative Appendix Q: Addenda Description Information	62

NOTE

Approved addenda, errata, or interpretations for this guideline can be downloaded free of charge from the ASHRAE website at www.ashrae.org/technology.

© 2019 ASHRAE

1791 Tullie Circle NE · Atlanta, GA 30329 · www.ashrae.org · All rights reserved.

ASHRAE is a registered trademark of the American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc.

(This foreword is not part of this guideline. It is merely informative and does not contain requirements necessary for conformance to the guideline.)

FOREWORD

The Commissioning Process (Cx) is a quality-focused process for enhancing the delivery of a project by achieving, validating, and documenting the performance of facility elements in meeting the objectives and criteria of the Owner. Cx extends through all phases of new or major renovation projects, from predesign to Owner occupancy and operation, with tasks during each phase to ensure verification of design, construction, and operator training.

Whereas ASHRAE/IES Standard 202 defines the minimum acceptable Cx for a project, ASHRAE Guideline 0 outlines best practices and establishes the order of phases in which the components of the Cx are best implemented. It provides a template for Cx Plans for specific facility elements or assemblies, and establishes common content that serves as a uniform method for achieving different levels of commissioning and meeting varying Owner's requirements. The guideline also serves as the foundation for authoring technical commissioning guidelines more narrowly targeted and focused on specific applications.

Appendices are included to assist in further understanding the Cx. Based on specific project experiences, they suggest ways to improve current practices and illustrate a variety of Cx applications, with examples for developing the Owner's Project Requirements, Basis of Design, design criteria, design concepts, verification and functional performance testing requirements, operator training, and more.

This 2019 edition of ASHRAE Guideline 0 updates terminology to reflect an evolving whole-building Commissioning Process (Cx) and harmonizes terminology and its usage with that of ASHRAE/IES Standard 202.

1. PURPOSE

1.1 The purpose of this guideline is to describe a Commissioning Process (Cx) capable of verifying that the facility and its systems meet the Owner's Project Requirements (OPR).

2. SCOPE

2.1 The procedures, methods, and documentation requirements in this guideline describe each phase of the project delivery and the associated Commissioning Processes from predesign through occupancy and operation, without regard to specific elements, assemblies, or systems.

2.2 This guideline provides the following:

- a. Overview of Commissioning Process Activities
- b. Description of the Commissioning Processes for each project phase
- c. Requirements for acceptance during each phase
- d. Requirements for documentation during each phase
- e. Requirements for training of operations and maintenance (O&M) personnel

3. UTILIZATION

3.1 The application of this guideline depends on the OPR and how the project is designed, built, and operated. The process

described in this guideline is written for a generic project and must be adapted to each specific project.

3.2 This guideline describes the Cx and is supplemented by companion technical guidelines. A technical guideline describes the specific details to properly implement the Cx relative to a specific facility system or assembly. Informative Appendix A in this guideline provides the required format for developing technical guidelines for the Cx.

4. DEFINITIONS

4.1 Terminology

acceptance: a formal action, taken by a person with appropriate authority (which may or may not be contractually defined), to declare that some aspect of the project meets defined requirements, thus permitting subsequent activities to proceed.

Basis of Design (BoD): a document that records the concepts, calculations, decisions, and product selections used to meet the OPR and to satisfy applicable regulatory requirements, standards, and guidelines. The document includes both narrative descriptions and lists of individual items that support the design process.

checklists: verification checklists that are developed and used during all phases of the Cx to verify that the OPR is being achieved. These include checklists for general verification, plus testing, training, and other specific requirements.

Commissioning Process (Cx): a quality-focused process for enhancing the delivery of a project. The process focuses on verifying and documenting that all of the commissioned systems and assemblies are planned, designed, installed, tested, operated, and maintained to meet the OPR.

construction checklist: a form used by the Project Team to verify that appropriate materials and components are on-site, ready for installation, correctly installed, functional, and in compliance with the OPR. See *checklists*.

construction documents: these include a wide range of documents that vary from project to project and with the Owner's needs, regulations, laws, and jurisdictional requirements. Construction documents usually include the project manual (specifications), plans (drawings), and general terms and conditions of the contract.

Construction Team: this consists of professionals responsible for providing materials and labor to construct the systems and assemblies in the project. Where a construction project follows a design/build approach, the Construction Team includes licensed design professionals who are part of the Design Team.

contract documents: include a wide range of documents that vary from project to project and with the Owner's needs, regulations, laws, and jurisdictional requirements. Contract documents frequently include price agreements, the construction management process, subcontractor agreements or requirements, requirements and procedures for submittals, changes, and other construction requirements, timeline for completion, and the construction documents.